BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT29475

APPROVED SCHEDULE - B

BTP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018

Excavation of Temporary Immersion Tank for Lord Ganesh Idols at Doddabommasandra Lake in Ward No. 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRADEEPA K A	
				In Figures	In Words
1	25.2	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	163.76	Rupees One Hundred Sixty Three and Seventy Six Paise Only
2	187.5	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary Soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	197.58	Rupees One Hundred Ninety Seven and Fifty Eight Paise Only
3	187.5	Above 1.5 Mtrs Depth Add 25% Extra	Cum	244.75	Rupees Two Hundred Forty Four and Seventy Five Paise Only
4	820	Code 0516 - Providing Plastic Sheet etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	5.696	Rupees Five and Sixty Nine Paise Only
5	165	Supply of water Through water Tank for filling Tank etc., complete and as per the directions of the Engineer-in-charge of the work	Each	320.4	Rupees Three Hundred Twenty and Forty Paise Only
6	2.5	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	790.32	Rupees Seven Hundred Ninety and Thirty Two Paise Only
7	66	Hire charge of pumping water 3.5 KL/hr capacity Pump etc., complete and as per the directions of the Engineer-in-charge of the work	Hr	48.95	Rupees Forty Eight and Ninety Five Paise Only
8	165	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc., complete and as per the directions of the Engineer-in-charge of the work	Days	255.43	Rupees Two Hundred Fifty Five and Forty Three Paise Only
9	480	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis etc., complete and as per the directions of the Engineer-in-charge of the work	Mtrs	64	Rupees Sixty Four Only
10	13200	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc., complete and as per the directions of the Engineer-in-charge of the work	Sft	7.35	Rupees Seven and Thirty Five Paise Only
11	165	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc., complete and as per the directions of the Engineer-in-charge of the work	Rft	17	Rupees Seventeen Only
12	220	Hire Charge for Armless Plastic Chairs etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	4	Rupees Four Only
13	110	Hire Charge for Wooden Table of Size 6ft x 2ft etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	40	Rupees Forty Only
14	1100	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire etc., complete and as per the directions of the Engineer-in-charge of the work	Mtrs	9	Rupees Nine Only
15	66	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling etc., complete and as per the directions of the Engineer-in-charge of the work	Hr	622.11	Rupees Six Hundred Twenty Two and Eleven Paise Only

Signature of the contractor

Executive Engine

	roved Qty.	Description	Unit	Approved Tender Rates of PRADEEPA K A	
				In Figures	In Words
	88	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	285	Rupees Two Hundred Eighty Five Only
7	5	Hire charges compoment name 1087 Crane charges etc., complete and as per the directions of the Engineer-in-charge of the work	Day	3942.7	Rupees Three Thousand Nine Hundred Forty Two and Seventy Paise Only
18	328.9	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	79.21	Rupees Seventy Nine and Twenty One Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92